				DEPARTMENT	ATE OF UTAH OF NATURAL RESO OIL, GAS AND M		AMEN	FOR			
		APPLICATIO	N FOR F	PERMIT TO DRILL			1. WELL NAME and NUMBER 14-13D	.45 BTR			
2. TYPE OF WORK	DRILL NEW WE	ELL REEI	NTER P&A	WELL DEEPEN V	VELL		3. FIELD OR WILDCAT				
4. TYPE OF WELL		Oil Well	Coalbe	d Methane Well: NO			5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATO	PR	BIL	L BARRET	T CORP			7. OPERATOR PHONE	2-8164			
8. ADDRESS OF OPER				), Denver, CO, 80202			9. OPERATOR E-MAIL BHilgers@billb		om		
10. MINERAL LEASE N (FEDERAL, INDIAN, OF	UMBER R STATE)			11. MINERAL OWNERSH	IIP AN 📵 STATE 🧐	FEE (	12. SURFACE OWNERSHIP FEDERAL INDIAN	STATE	~	E ( )	
13. NAME OF SURFAC	20G0005608 E OWNER (if box	12 = 'fee')			0 0		14. SURFACE OWNER PHONE				
15. ADDRESS OF SUR	FACE OWNER (if b	oox 12 = 'fee')					16. SURFACE OWNER E-MAIL	. (if box 12 :	= 'fee')		
17. INDIAN ALLOTTEE	OR TRIBE NAME			18. INTEND TO COMMI		FROM	19. SLANT				
(if box 12 = 'INDIAN')	Uintah and Ouray			MULTIPLE FORMATION YES (Submit Co	mmingling Applicati	on) NO 📵	VERTICAL DIRECTION	AL 📵 HO	ORIZONT	AL 🔵	
20. LOCATION OF W	ELL		FO	OTAGES	QTR-QTR	SECTION	TOWNSHIP	NGE	МЕ	RIDIAN	
LOCATION AT SURFA	ACE		532 FSL	. 2080 FWL	SESW	13	4.08	.0 W		U	
Top of Uppermost P	roducing Zone		808 FSL	. 1979 FWL	SESW	13	0 S 5	.0 W		U	
At Total Depth			810 FSL	. 1980 FWL	SESW	12	4.0 S 5	.0 W		U	
21. COUNTY	DUCHESNE			22. DISTANCE TO NEAR	EST LEASE LINE (F. 810	NY	23. NUMBER OF ACRES IN DR		•		
				25. DISTANCE TO NEAR (Applied For Drilling of	FST WELL IN SAM Completed 122	ВО	26. PROPOSED DEPTH MD: 7963	TVD: 7948			
27. ELEVATION - GRO	UND LEVEL			28. BOND NUMBER			29. SOURCE OF DRILLING WA WATER RIGHTS APPROVAL NU		PI ICARI	F	
	6029				LPM8874725			180			
String   Hole Size	Casing Sizo	Longth	W gh	He Casing, ade & Thread	and Cement Info	rmation	Cement	Sacks	Yield	Weight	
Cond 26	Casing Size	Length 0 - 80	65	Unknown	8.8		No Used	0	0.0	0.0	
<b>Surf</b> 12.25	9.625	0 2 0	36.0	J-55 ST&C	8.8	Halliburto	on Light , Type Unknown	280	3.16	11.0	
						Halliburton	Premium , Type Unknown	210	1.36	14.8	
<b>Prod</b> 8.75	.62	0 - 7963	17.0	P-110 LT&C	9.6		Unknown	630	2.31	11.0	
				<u> </u>			Unknown	720	1.42	13.5	
				АТ	TACHMENTS						
V	ERIFY THE FOLI	LOWING ARE	ATTAC	HED IN ACCORDANC	CE WITH THE UTA	AH OIL AND GAS	S CONSERVATION GENERA	L RULES			
WELL PLAT OF	R MAP PREPARED E	BY LICENSED S	URVEYOR	OR ENGINEER	СОМ	PLETE DRILLING F	PLAN				
AFFIDAVIT OF	STATUS OF SURFA	CE OWNER AGI	REEMENT	(IF FEE SURFACE)	FORM	15. IF OPERATOR	IS OTHER THAN THE LEASE OW	NER			
DIRECTIONAL	SURVEY PLAN (IF I	DIRECTIONALL	Y OR HO	RIZONTALLY DRILLED)	<b>№</b> торо	GRAPHICAL MAP					
NAME Venessa Langr	nacher		TITLE S	enior Permit Analyst		PHONE 303 3	312-8172				
SIGNATURE			DATE 0	6/21/2012		EMAIL vlangm	nacher@billbarrettcorp.com				
API NUMBER ASSIGN	<b>ED</b> 4301351495000	00		APPROVAL							

# BILL BARRETT CORPORATION DRILLING PLAN

#### 14-13D-45 BTR

SE SW, 532' FSL and 2080' FWL, Section 13, T4S-R5W, USB&M (surface hole) SE SW, 810' FSL and 1980' FWL, Section 13, T4S-R5W, USB&M (bottom hole) Duchesne County, Utah

# 1 - 2. <u>Estimated Tops of Geological Markers and Formations Expected to Contain Water, Oil and Gas and Other Minerals</u>

<u>Formation</u>	Depth – MD	Depth - TVD
Lower Green River*	4,176'	4,167'
Douglas Creek	5,036'	5,022'
Black Shale	5,812'	5,798
Castle Peak	6,068'	6,0 1
Uteland Butte	6,440'	,426'
Wasatch*	6,673'	6,659'
TD	7,963'	7,948'

#### \*PROSPECTIVE PAY

The Wasatch and the Lower Green iv are parary objectives for oil/gas.

Base of Useable W ter = 54.

# 3. BOP and Pressure Contain fie t Data

Depth Interval	BOP Equipment
0-2,000	To pressure control required
2,0002-10	11" 5000# Ram Type BOP
	11" 5000# Annular BOP
- Diming spool to a	ccommodate choke and kill lines;



- Ancillary equipment and choke manifold rated at 5,000 psi. All BOP and BOPE tests will be in accordance with the requirements of onshore Order No. 2;
- The BLM and the State of Utah Division of Oil, Gas and Mining will be notified 24 hours in advance of all BOP pressure tests.
- BOP hand wheels may be underneath the sub-structure of the rig if the drilling rig used is set up To operate most efficiently in this manner.

#### 4. <u>Casing Program</u>

Hole Size	SETTING	DEPTH	Casing	Casing	Casing		
	(FROM)	<u>(TO)</u>	Size	Weight	<b>Grade</b>	<b>Thread</b>	Condition
26"	Surface	80'	16"	65#			
12 1/4"	Surface	2,000'	9 5/8"	36#	J or K 55	ST&C	New
8 3/4"	Surface	TD	5 ½"	17#	P-110	LT&C	New

#### 5. <u>Cementing Program</u>


16" Conductor Casing	Grout
9 5/8" Surface Casing	Lead: 280 sx Halliburton Light Premium with additives
	mixed at 11.0 ppg (yield = $3.16 \text{ ft}^3/\text{sx}$ ) circulated to surface
	with 75% excess. TOC @ Surface
	Tail: 210 sx Halliburton Premium Plus cement with
	additives mixed at 14.8 ppg (yield = $1.36 \text{ ft}^3/\text{sx}$ ), calculated
	hole volume with 75% excess. TOC @ 1,500'
5 ½" Production Casing	Lead: 630 sx Tuned Light cement with additives mixed at
	11.0 ppg (yield = $2.31 \text{ ft}^3/\text{sx}$ ). TOC @ 1,200'
	Tail: 720 sx Halliburton Econocem cement with additives
	mixed at 13.5 ppg (yield = $1.42 \text{ ft}^3/\text{sx}$ ). Top of cement to
	be determined by log and sample evaluation; estimated TOC
	@ 5,312'

#### 6. Mud Program

<u>Interval</u>	<u>Weight</u>	<u>Viscosity</u>	Fluid Loss (API filtrate)	Remarks
0'-80'	8.3 - 8.8	26 – 36	NC	reshwater Spud Mud Fluid System
80' – 2,000'	8.3 - 8.8	26 – 36	y A	Freshwater Spud Mud Fluid System
2,000' – TD	8.6 – 9.6	42 52	20 cc or less	DAP Polymer Fluid System

Note: Sufficient mud materia, to ma tain mud properties, control lost circulation and to contain "kicks" will be available at "en tite. BBC may require minor amounts of diesel to be added to its fluid system in order to reduce or que and drag.

## 7. Testing, Logsing and Core Programs



#### 8. Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures or other hazards are anticipated.

Maximum anticipated bottom hole pressure equals approximately 3967 psi\* and maximum anticipated surface pressure equals approximately 2219 psi\*\* (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

<sup>\*</sup>Max Mud Wt x 0.052 x TD = A (bottom hole pressure)

<sup>\*\*</sup>Maximum surface pressure = A - (0.22 x TD)

Bill Barrett Corporation **Drilling Program** 14-13D-45 BTR Duchesne County, Utah

#### 9. **Auxiliary Equipment**

- a) Upper kelly cock; lower Kelly cock will be installed while drilling
- b) Inside BOP or stab-in valve (available on rig floor)
- c) Safety valve(s) and subs to fit all string connections in use Mud monitoring will be visually observed

#### **Location and Type of Water Supply** 10.


Water for the drilling and completion will be trucked from the Duchesne City Culinary Water Dock located in Sec. 1, T4S, R5W water right number 43-180.

#### 11. **Drilling Schedule**

Returned Unapproved



## LAKE CANYON & BLACK TAIL RIDGE CEMENT VOLUMES




roc Ction Hole Data	<u>ı:</u>		Calculated Data:		
Total Depth:	7,963'	ì	Lead Volume:	1444.3	ft³
Top of Cement:	1,500'	1	Lead Fill:	3,812'	
Top of Tail:	5,312'	1	Tail Volume:	1004.5	ft³
OD of Hole:	8.750"	1	Tail Fill:	2,651'	
OD of Casing:	5.500"	1			
Cement Data:			Calculated # of	Sacks:	
Cement Data:  Lead Yield:	2.31	ft³/sk	Calculated # of  # SK's Lead:	Sacks: 630	
		ft°/sk ft³/sk			


# 14-13D-45 BTR Proposed Cementing Program


b Recommendation		Sui	face Casi
Lead Cement - (1500' - 0')			
Halliburton Light Premium	Fluid Weight:	11.0	lbm/gal
5.0 lbm/sk Silicalite Compacted	Slurry Yield:	3.16	ft <sup>3</sup> /sk
0.25 lbm/sk Kwik Seal	Total Mixing Fluid:	19.48	Gal/sk
0.125 lbm/sk Poly-E-Flake	Top of Fluid:	0'	•
2.0% Bentonite	Calculated Fill:	1,500'	
	Volume:	146.41	bbl
	Proposed Sacks:	280	sks
Tail Cement - (TD - 1500')			1
Premium Cement	Fluid Weight:	14.8	lbr /g 1
2.0% Calcium Chloride	Slurry Yield:	1.36	°t°/sk
	Total Mixing Fluid:	1.5	Gal/sk
	Top of Fkad:		•
	Calcul (e. F. L.	500'	
	V lame:	48.80	bbl
	Photocd Sacks:	210	sks


Job Recommendation		Produc	tion Casing
Lead Cement - (5310' - 1500')			
Tuned Light System	Fluid Weight:	11.0	lbm/gal
	Slurry Yield:	2.31	ft <sup>3</sup> /sk
Return	Total Mixing Fluid:	10.65	Gal/sk
	Top of Fluid:	1,500'	
	Calculated Fill:	3,812'	
	Volume:	257.23	bbl
	Proposed Sacks:	630	sks
Tail Cement - (7963' - 5312')			
Econocem <sup>TM</sup> System	Fluid Weight:	13.5	lbm/gal
0.125 lbm/sk Poly-E-Flake	Slurry Yield:	1.42	ft <sup>3</sup> /sk
1.0 lbm/sk Granulite TR 1/4	Total Mixing Fluid:		Gal/sk
	Top of Fluid:	5,312'	
	Calculated Fill:	2,651'	
	Volume:	178.90	bbl
	Proposed Sacks:	720	sks




21, Received: **2012** 












Bill Barrett Corp.
Project: Duchesne Co., UT (NAD27)
Site: Sec.13-T4S-R5W
Well: #14-13D-45 BTR
Wellbore: Wellbore #1
Design: Design #1
Latitude: 40° 7' 39.011 N
Longitude: 110° 23' 59.752 W
Ground Level: 6031.00







# Bill Barrett Corp.

**Duchesne Co., UT (NAD27)** Sec.13-T4S-R5W

Standard Planning Report

07 June, 2012





Planning Report



40° 7' 39.011 N

EDM 5000.1 Single User Db Database:

Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27) Sec.13-T4S-R5W Site: Well: #14-13D-45 BTR

Wellbore: Wellbore #1 Design #1 Design:

**Local Co-ordinate Reference:** 

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well #14-13D-45 BTR WELL @ 6046.00usft WELL @ 6046.00usft

True

Minimum Curvature

Project Duchesne Co., UT (NAD27)

US State Plane 1927 (Exact solution) Map System:

NAD 1927 (NADCON CONUS) Geo Datum:

Utah Central 4302 Map Zone:

System Datum:

Mean Sea Level

Sec.13-T4S-R5W Site

Northing: 655,527.921 usft Site Position: Latitude: 40° 7' 40.192 N From: Lat/Long Easting: 2,309,917.097 usft Longitude: 110° 23' 29.872 W **Position Uncertainty:** 0.00 usft 0.71 °

Slot Radius: 13-3/16" **Grid Convergence:** 

Well #14-13D-45 BTR

**Well Position** +N/-S -119.38 usft Northing: 655,379.794 usft Latitude: +E/-W

-2,320.88 usft Easting: 2,307,597.876 usft

Longitude:
Group 1 L vel: 110° 23' 59.752 W **Position Uncertainty** 0.00 usft Wellhead Elevation: usft 6,031.00 usft

Wellbore Wellbore #1 Magnetics **Model Name** Sample Date Dip Angle Field Strength (nT) IGRF2010 06/07/12 65.77 52,166

Design #1 Design **Audit Notes:** Version: Tie On Depth: 0.00 **Vertical Section:** +N/-S +E/-W Direction (usft) (usft) (°) 0.00 0.00 339.82

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,729.17	6.29	339.82	2,727.91	32.39	-11.91	1.00	1.00	0.00	339.82	
4,783.73	6.29	339.82	4,770.09	243.72	-89.60	0.00	0.00	0.00	0.00	
5,412.90	0.00	0.00	5,398.00	276.11	-101.50	1.00	-1.00	0.00	180.00	14-13D-45 BTR Tgt
7,962.90	0.00	0.00	7,948.00	276.11	-101.50	0.00	0.00	0.00	0.00	



Planning Report



Database: EDM 5000.1 Single User Db

Company: Bill Barrett Corp.

 Project:
 Duchesne Co., UT (NAD27)

 Site:
 Sec.13-T4S-R5W

 Well:
 #14-13D-45 BTR

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well #14-13D-45 BTR WELL @ 6046.00usft WELL @ 6046.00usft

Minimum Curvature

sigii.	Design #1								
nned Survey									
Measured Depth (usft)	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
(usit)	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(7100usit)	( / Ioousit)	(7100usit)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	000	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00		0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	1.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00		0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	_0.0	0.00	0.00
	0.00			0.00	0.00	0.00		0.00	0.00
1,100.00		0.00	1,100.00				00		
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0 00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	2.0	0.00	0.00	0.00
1 500 00	0.00	0.00	1 500 00	0.00	0.00		0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	100	0	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00		0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00		0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
9 5/8" Csg.									
2,000.00	0.00	0.00	2,600.	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 1.	.00								
2,100.00	0.00	0.00	2,100,00	0.00	0.00	0.00	0.00	0.00	0.00
	0.00		2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
Green River									
2,190.00	0 90	331 12	2,190.00	0.66	-0.24	0.71	1.00	1.00	0.00
2,200.00	17.0	39.82	2,199.99	0.82	-0.30	0.87	1.00	1.00	0.00
2,300.00	2.0	339.82	2,299.96	3.28	-1.20	3.49	1.00	1.00	0.00
2,400.		000.00	0.000.00	7.07	0.74	7.05	4.00	4.00	0.00
	.00	339.82	2,399.86	7.37	-2.71	7.85	1.00	1.00	0.00
2,500.00	4.00	339.82	2,499.68	13.10	-4.82	13.96	1.00	1.00	0.00
2,600.00	5.00	339.82	2,599.37	20.46	-7.52	21.80	1.00	1.00	0.00
2,700.00	6.00	339.82	2,698.90	29.46	-10.83	31.39	1.00	1.00	0.00
Start 2054.56	hold at 2729.17	7 MD							
2,729.17	6.29	339.82	2,727.91	32.39	-11.91	34.51	1.00	1.00	0.00
2,800.00	6.29	339.82	2,798.31	39.68	-14.59	42.27	0.00	0.00	0.00
2,900.00	6.29	339.82	2,897.71	49.96	-18.37	53.23	0.00	0.00	0.00
Mahogany									
2.999.89	6.29	339.82	2,997.00	60.24	-22.14	64.18	0.00	0.00	0.00
					00.45	04.40	0.00	0.00	
3,000.00	6.29	339.82	2,997.11	60.25	-22.15	64.19	0.00	0.00	0.00
3,100.00	6.29	339.82	3,096.50	70.53	-25.93	75.15	0.00	0.00	0.00
3,200.00	6.29	339.82	3,195.90	80.82	-29.71	86.11	0.00	0.00	0.00
3,300.00	6.29	339.82	3,295.30	91.11	-33.49	97.07	0.00	0.00	0.00
3,400.00	6.29	339.82	3,394.70	101.39	-37.27	108.03	0.00	0.00	0.00
3,500.00	6.29	339.82	3,494.09	111.68	-41.05	118.99	0.00	0.00	0.00
3,600.00	6.29	339.82	3,593.49	121.96	-44.84	129.94	0.00	0.00	0.00
3,700.00	6.29	339.82	3,692.89	132.25	-48.62	140.90	0.00	0.00	0.00
,									
3,800.00	6.29	339.82	3,792.29	142.54	-52.40	151.86	0.00	0.00	0.00
3,900.00	6.29	339.82	3,891.68	152.82	-56.18	162.82	0.00	0.00	0.00
4,000.00	6.29	339.82	3,991.08	163.11	-59.96	173.78	0.00	0.00	0.00
4,100.00	6.29	339.82	4,090.48	173.39	-63.74	184.74	0.00	0.00	0.00
TGR3									
4 476 00	6.29	339.82	4,167.00	181.31	-66.65	193.18	0.00	0.00	0.00
4,176.98 4,200.00	6.29		4,189.88						



Planning Report



Database: EDM 5000.1 Single User Db

Company: Bill Barrett Corp.

 Project:
 Duchesne Co., UT (NAD27)

 Site:
 Sec.13-T4S-R5W

 Well:
 #14-13D-45 BTR

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference: TVD Reference:

MD Reference:
North Reference:

**Survey Calculation Method:** 

Well #14-13D-45 BTR WELL @ 6046.00usft WELL @ 6046.00usft

True
Minimum Curvature

1:	Design #1								
ed Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,300.00	6.29	339.82	4,289.27	193.97	-71.30	206.66	0.00	0.00	0.00
4,400.00		339.82	4,388.67	204.25	-75.09	217.62	0.00	0.00	0.00
4,500.00		339.82	4,488.07	214.54	-78.87	228.58	0.00	0.00	0.00
4,600.00		339.82	4,587.47	224.83	-82.65	239.53	0.00	0.00	0.00
4,700.00	6.29	339.82	4,686.87	235.11	-86.43	250.49	0.00	0.00	0.00
Start Drop	-1.00								
4,783.73	6.29	339.82	4,770.09	243.72	-89.60	259.67	0.00	500	0.00
4,800.00	6.13	339.82	4,786.27	245.38	-90.20	261.43	1.00		0.00
4,900.00	5.13	339.82	4,885.78	254.58	-93.59	271.24	1.00	.00	0.00
5,000.00	4.13	339.82	4,985.45	262.16	-96.37	279.31	1.00	11111	0.00
		333.02	4,900.40	202.10	-30.37	273.51	1.00	1.00	0.00
Douglas C		220.00	E 000 00	064.50	07.04	004.00	200	4.00	0.00
5,036.63		339.82	5,022.00	264.52	-97.24	281.83	700	-1.00 1.00	0.00
5,100.00		339.82	5,085.25	268.10	-98.56	285 64	1.00	-1.00	0.00
5,200.00		339.82	5,185.15	272.40	-100.14	(0.2	1.00	-1.00	0.00
5,300.00	1.13	339.82	5,285.10	275.07	-101.12	2 0	1.00	-1.00	0.00
5,400.00	0.13	339.82	5,385.10	276.10	-101 0	294 7	1.00	-1.00	0.00
Start 2550.	00 hold at 5412.90	MD - 3PT Marl	ker - 14-13D-45 l	BTR Tgt 🚄 🔠					
5,412.90		0.00	5,398.00	276.1	101.50	294.18	1.00	-1.00	0.00
5,500.00		0.00	5,485.10	76.11	-101.50	294.18	0.00	0.00	0.00
5,600.00		0.00	5,585.1	2 11	-101.50	294.18	0.00	0.00	0.00
5,700.00		0.00	5,685.10	276.11	-101.50	294.18	0.00	0.00	0.00
,									
5,800.00	0.00	0.00	77.	276.11	-101.50	294.18	0.00	0.00	0.00
Black Shal									
5,812.90	0.00	(0	5,798.00	276.11	-101.50	294.18	0.00	0.00	0.00
5,900.00	0.00	00	5,885.10	276.11	-101.50	294.18	0.00	0.00	0.00
6,000.00	0 00	<b>9</b> 0	5,985.10	276.11	-101.50	294.18	0.00	0.00	0.00
Castle Pea	k								
6,068	0.0	0.00	6,054.00	276.11	-101.50	294.18	0.00	0.00	0.00
6,100.0	0.00	0.00	6,085.10	276.11	-101.50	294.18	0.00	0.00	0.00
6,200.00		0.00	6,185.10	276.11	-101.50	294.18	0.00	0.00	0.00
6,300.00		0.00	6,285.10	276.11	-101.50	294.18	0.00	0.00	0.00
6,400.00		0.00	6,385.10	276.11	-101.50	294.18	0.00	0.00	0.00
		0.00	0,365.10	270.11	-101.50	294.10	0.00	0.00	0.00
Uteland Bu		0.00	0.400.00	070 44	404.50	004.40	0.00	0.00	0.00
6,440.90	0.00	0.00	6,426.00	276.11	-101.50	294.18	0.00	0.00	0.00
CR1									
6,499.90	0.00	0.00	6,485.00	276.11	-101.50	294.18	0.00	0.00	0.00
6,500.00		0.00	6,485.10	276.11	-101.50	294.18	0.00	0.00	0.00
CR1A Base									
6,540.90		0.00	6,526.00	276.11	-101.50	294.18	0.00	0.00	0.00
6,600.00		0.00	6,585.10	276.11	-101.50	294.18	0.00	0.00	0.00
Wasatch	3.50	0.00	5,555.10	2. 0. 11	.01.00	201.10	0.00	0.00	0.00
6,673.90	0.00	0.00	6,659.00	276.11	-101.50	294.18	0.00	0.00	0.00
0,073.90	0.00	0.00	0,059.00	2/0.11	-101.50	∠94.10	0.00	0.00	0.00
6,700.00		0.00	6,685.10	276.11	-101.50	294.18	0.00	0.00	0.00
6,800.00	0.00	0.00	6,785.10	276.11	-101.50	294.18	0.00	0.00	0.00
CR2									
6,825.90	0.00	0.00	6,811.00	276.11	-101.50	294.18	0.00	0.00	0.00
6,900.00		0.00	6,885.10	276.11	-101.50	294.18	0.00	0.00	0.00
7,000.00		0.00	6,985.10	276.11	-101.50	294.18	0.00	0.00	0.00
			,	-					
CR3									
7,073.90		0.00	7,059.00	276.11	-101.50	294.18	0.00	0.00	0.00
7,100.00		0.00	7,085.10	276.11	-101.50	294.18	0.00	0.00	0.00
7,200.00		0.00	7,185.10	276.11	-101.50	294.18	0.00	0.00	0.00
7,300.00	0.00	0.00	7,285.10	276.11	-101.50	294.18	0.00	0.00	0.00



Planning Report



Database: EDM 5000.1 Single User Db

Company: Bill Barrett Corp.

Design:

 Project:
 Duchesne Co., UT (NAD27)

 Site:
 Sec.13-T4S-R5W

 Well:
 #14-13D-45 BTR

 Wellbore:
 Wellbore #1

Design #1

Local Co-ordinate Reference: TVD Reference: MD Reference:

Survey Calculation Method:

North Reference:

Well #14-13D-45 BTR WELL @ 6046.00usft WELL @ 6046.00usft

Minimum Curvature

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
7,400.00	0.00	0.00	7,385.10	276.11	-101.50	294.18	0.00	0.00	0.00
7,500.00 7,600.00	0.00 0.00	0.00 0.00	7,485.10 7,585.10	276.11 276.11	-101.50 -101.50	294.18 294.18	0.00 0.00	0.00 0.00	0.00 0.00
CR4 - CR4A									
7,662.90 7,700.00 7,800.00	0.00 0.00 0.00	0.00 0.00 0.00	7,648.00 7,685.10 7,785.10	276.11 276.11 276.11	-101.50 -101.50 -101.50	294.18 294.18 294.18	0.00 0.00 0.00	0.00 0.00 5	0.00 0.00 0.00
CR5									
7,811.90 7,900.00	0.00 0.00	0.00 0.00	7,797.00 7,885.10	276.11 276.11	-101.50 -101.50	294.18 294.18	0.00 0.00	0.00	0.00 0.00
TD at 7962.90	)								
7,962.90	0.00	0.00	7,948.00	276.11	-101.50	294.18	000	0.00	0.00

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+EV-W (ust)	It thing (usft)	Easting (usft)	Latitude	Longitude
14-13D-45 BTR Tgt - plan hits target ce - Rectangle (sides		0.00 00 D2,550.0	5,398.00	76.11	101.50	655,654.640	2,307,492.985	40° 7' 41.740 N	110° 24' 1.058 W

Casing Points						
	Depth Lepth (usft)		Name	Casing Diameter (")	Hole Diameter (")	
	20.00 2,000.00	9 5/8" Csg.		9-5/8	12-1/4	



Planning Report



EDM 5000.1 Single User Db Database: Company:

Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27) Sec.13-T4S-R5W Site: Well: #14-13D-45 BTR Wellbore: Wellbore #1 Design: Design #1

Local Co-ordinate Reference: TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well #14-13D-45 BTR WELL @ 6046.00usft WELL @ 6046.00usft

Minimum Curvature

nations								
	Measured Depth (usft)	Vertical Depth (usft)		Name		Lithology	Dip (°)	Dip Direction (°)
	2,190.00	2,190.00	Green River				0.00	
	2,999.89	2,997.00	Mahogany				0.00	
	4,176.98	4,167.00	TGR3				0.00	
	5,036.63	5,022.00	Douglas Creek				0.00	
	5,412.90	5,398.00	3PT Marker				0.00	
	5,812.90	5,798.00	Black Shale				0.00	•
	6,068.90	6,054.00	Castle Peak				0.00	
	6,440.90	6,426.00	Uteland Butte				0.00	
	6,499.90	6,485.00	CR1				<b>2</b> .0	
	6,540.90	6,526.00	CR1A Base				0.00	
	6,673.90	6,659.00	Wasatch				00	
	6,825.90	6,811.00	CR2			_ ~~	0.00	
	7,073.90	7,059.00	CR3				0.00	
	7,662.90	7,648.00	CR4A			JP'	0.00	
	7,662.90	7,648.00	CR4		102		0.00	
	7,811.90	7,797.00	CR5		1 1 W		0.00	

Plan Annotations		4		
Measured	Vertical	Local ( vork	tates	Comment
Depth	Depth	+N/-S	+E/-W	
(usft)	(usft)	(u. 1)	(usft)	
2,100.00	2,100,00	0.00	0.00	Start Build 1.00
2,729.17	2,77.	32.39	-11.91	Start 2054.56 hold at 2729.17 MD
4,783.73	4,7 0	243.72	-89.60	Start Drop -1.00
5,12.90	398.00	276.11	-101.50	Start 2550.00 hold at 5412.90 MD
7,912.90	7,948.00	276.11	-101.50	TD at 7962.90



# Bill Barrett Corp.

**Duchesne Co., UT (NAD27)** Sec.13-T4S-R5W

Anticollision Report

Sharewell Energy Services



Anticollision Report

MD Reference:



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Design #1

 Reference Site:
 Sec.13-T4S-R5W

 Site Error:
 0.00 usft

 Reference Well:
 #14-13D-45 BTR

 Well Error:
 0.00 usft

 Reference Wellbore
 Wellbore #1

Local Co-ordinate Reference:
TVD Reference:

Well #14-13D-45 BTR WELL @ 6046.00usft WELL @ 6046.00usft

North Reference: True

Survey Calculation Method: Minimum Curvature

Output errors are at 2.00 sigma

Database: EDM 5000.1 Single User Db

Offset TVD Reference: Offset Datum

Reference Design #1

Reference Design:

Filter type: NO GLOBAL FILTER: Using user defined selection & filtering criteria

Interpolation Method: Stations Error Model: ISCWSA

 Depth Range:
 Unlimited
 Scan Method:
 Closest Approach 3D

 Results Limited by:
 Maximum center-center distance of 9,999.98 usft
 Error Surface:
 Elliptical Conic

 Warning Levels Evaluated at:
 2.00 Sigma
 Casing Method:
 Not applied

 Survey Tool Program
 Date
 06/07/12

 From (usft)
 To (usft)
 Survey (Wellbore)
 Tool Name
 Description

 0.00
 7,962.90
 Design #1 (Wellbore #1)
 MWD
 MWD - Standard

Summary					4	~ ( )		
Site Name Offset Well - We	ellbore - Design		Reference Measured Depth (usft)	Offset Measured Depts	Get been prices sft)	ce Between Ellipses (usft)	Separation Factor	Warning
Sec.13-T4S-R5W								
#16-13D-45 BTF #16-13D-45 BTF	R - Wellbore #1 - Design #1 R - Wellbore #1 - Design #1 R - Wellbore #1 - Design #1 R - Wellbore #1 - Design #1	bs.	6, 4.93 2,1 2 2,200.00 7,962.90	8,771.73 2,111.00 2,210.99 7,964.70	105.72 2,323.95 2,324.21 2,466.06	23.94 2,314.74 2,314.55 2,430.25	1.293 L 252.427 C 240.738 E 68.864 S	S

Offset De	sign	Sec.13-	T4 -R5	- 13h 13	-45 BTR -	- Wellbore #1	- Design #1						Offset Site Error:	0.00 usft
Survey Prog													Offset Well Error:	0.00 usft
Refer	_	0 Se		Semi Major					Dista					
Measured Depth			Vertical Depth	Reference	Offset	Highside Toolface	Offset Wellbor		Between Centres	Between Ellipses	Minimum Separation	Separation Factor	Warning	
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)	+N/-S (usft)	+E/-W (usft)	(usft)	(usft)	(usft)	ractor		
0.00	0.00	12.00	12.00	0.00	0.01	87.43	104.28	2,320.87	2,323.21					
100.00	100.00	112.00	112.00	0.10	0.12	87.43	104.28	2,320.87	2,323.21	2,322.99	0.22	N/A		
200.00	200.00	212.00	212.00	0.32	0.35	87.43	104.28	2,320.87	2,323.21	2,322.54	0.67	3,480.177		
300.00	300.00	312.00	312.00	0.55	0.57	87.43	104.28	2,320.87	2,323.21	2,322.09	1.12	2,079.704		
400.00	400.00	412.00	412.00	0.77	0.80	87.43	104.28	2,320.87	2,323.21	2,321.64	1.57	1,482.945		
500.00	500.00	512.00	512.00	0.99	1.02	87.43	104.28	2,320.87	2,323.21	2,321.19	2.02	1,152.300		
600.00	600.00	612.00	612.00	1.22	1.25	87.43	104.28	2,320.87	2,323.21	2,320.75	2.47	942.218		
700.00	700.00	712.00	712.00	1.44	1.47	87.43	104.28	2,320.87	2,323.21	2,320.30	2.92	796.926		
800.00	800.00	812.00	812.00	1.67	1.70	87.43	104.28	2,320.87	2,323.21	2,319.85	3.36	690.456		
900.00	900.00	912.00	912.00	1.89	1.92	87.43	104.28	2,320.87	2,323.21	2,319.40	3.81	609.082		
1,000.00	1,000.00	1,012.00	1,012.00	2.12	2.15	87.43	104.28	2,320.87	2,323.21	2,318.95	4.26	544.867		
1,100.00	1,100.00	1,112.00	1,112.00	2.34	2.37	87.43	104.28	2,320.87	2,323.21	2,318.50	4.71	492.901		
1,200.00	1,200.00	1,212.00	1,212.00	2.57	2.59	87.43	104.28	2,320.87	2,323.21	2,318.05	5.16	449.984		
1,300.00	1,300.00	1,312.00	1,312.00	2.79	2.82	87.43	104.28	2,320.87	2,323.21	2,317.60	5.61	413.942		
1,400.00	1,400.00	1,412.00	1,412.00	3.02	3.04	87.43	104.28	2,320.87	2,323.21	2,317.15	6.06	383.245		
1,500.00	1,500.00	1,512.00	1,512.00	3.24	3.27	87.43	104.28	2,320.87	2,323.21	2,316.70	6.51	356.787		
1,600.00	1,600.00	1,612.00	1,612.00	3.47	3.49	87.43	104.28	2,320.87	2,323.21	2,316.25	6.96	333.747		
1,700.00	1,700.00	1,712.00	1,712.00	3.69	3.72	87.43	104.28	2,320.87	2,323.21	2,315.80	7.41	313.501		
1,800.00	1,800.00	1,812.00	1,812.00	3.92	3.94	87.43	104.28	2,320.87	2,323.21	2,315.35	7.86	295.571		
1,900.00	1,900.00	1,912.00	1,912.00	4.14	4.17	87.43	104.28	2,320.87	2,323.21	2,314.90	8.31	279.582		
2,000.00	2,000.00	2,012.00	2,012.00	4.37	4.39	87.43	104.28	2,320.87	2,323.21	2,314.45	8.76	265.233		
2,100.00	2,100.00	2,112.00	2,112.00	4.59	4.62	87.43	104.28	2,320.87	2,323.21	2,314.00	9.21	252.285		
2,200.00	2,199.99	2,211.99	2,211.99	4.81	4.84	107.63	104.28	2,320.87	2,323.48	2,313.82	9.66	240.606		



Anticollision Report



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Sec.13-T4S-R5W Reference Site: 0.00 usft Site Error: Reference Well: #14-13D-45 BTR Well Error: 0.00 usft

Reference Wellbore Wellbore #1 Reference Design: Design #1

Local Co-ordinate Reference:

Well #14-13D-45 BTR TVD Reference: WELL @ 6046.00usft WELL @ 6046.00usft MD Reference:

True North Reference:

**Survey Calculation Method:** Minimum Curvature

Output errors are at 2.00 sigma EDM 5000.1 Single User Db Database:

Offset TVD Reference: Offset Datum

urvey Prog	ram: 0-M	IWD											Office 4 18/- 11 F	0.00
	ram: U-IVI	Offs	et	Semi Major	Axis				Dista	ance			Offset Well Error:	0.00 us
easured	Vertical	Measured	Vertical	Reference	Offset	Highside	Offset Wellbor	e Centre	Between	Between	Minimum	Separation	Warning	
Depth (usft)	Depth (usft)	Depth (usft)	Depth (usft)	(usft)	(usft)	Toolface (°)	+N/-S	+E/-W	Centres (usft)	Ellipses (usft)	Separation (usft)	Factor		
							(usft)	(usft)				000.055		
2,300.00 2,400.00	2,299.96 2,399.86	2,311.96 2,411.86	2,311.96 2,411.86	5.04 5.26	5.07 5.29	107.68 107.77	104.28 104.28	2,320.87 2,320.87	2,324.27 2,325.60	2,314.17 2,315.05	10.10 10.55	230.055 220.451		
2,500.00	2,499.68	2,511.68	2,511.68	5.49	5.52	107.77	104.28	2,320.87	2,327.47	2,315.03	11.00	211.661		
2,600.00	2,599.37	2,611.37	2,611.37	5.72	5.74	108.06	104.28	2,320.87	2,329.90	2,318.45	11.45	203.568		
2,700.00	2,698.90	2,710.90	2,710.90	5.95	5.96	108.25	104.28	2,320.87	2,332.90	2,321.00	11.90	196.073		
2,729.17	2,727.91	2,739.91	2,739.91	6.02	6.03	108.32	104.28	2,320.87	2,333.88	2,321.85	12.03	193.987		
, -	,	,	,					,	,	,-				
2,800.00	2,798.31	2,810.31	2,810.31	6.19	6.19	108.49	104.28	2,320.87	2,336.35	2,323.99	12.36	189.06		
2,900.00	2,897.71	2,909.71	2,909.71	6.43	6.41	108.75	104.28	2,320.87	2,339.87	2,327.05	12.82	82 98		
3,000.00	2,997.11	3,009.11	3,009.11	6.68	6.63	109.00	104.28	2,320.87	2,343.43	2,330.14	13 29	6,335		
3,100.00	3,096.50	3,108.50	3,108.50	6.93	6.86	109.25	104.28	2,320.87	2,347.04	2,333.28	13	170.554		
3,200.00	3,195.90	3,207.90	3,207.90	7.19	7.08	109.50	104.28	2,320.87	2,350.70	2,336.	4.24	165.121		
3,300.00	3,295.30	3,307.30	3,307.30	7.45	7.30	109.75	104.28	2,320.87	2,354.40	33 8	14.71	160.013		
3,400.00	3,394.70	3,406.70	3,406.70	7.71	7.53	110.00	104.28	2,320.87	2 358.	42 20	15.19	155.203		
3,500.00	3,494.09	3,506.09	3,506.09	7.98	7.75	110.25	104.28	2,320.87	2,2 .93	,346.26	15.68	150.670		
3,600.00	3,593.49	3,605.49	3,605.49	8.25	7.97	110.50	104.28	2,320	2,36 .77	2,349.61	16.16	146.392		
3,700.00	3,692.89	3,704.89	3,704.89	8.52	8.20	110.75	104.28	2,5.20 6	369.65	2,353.00	16.65	142.352		
3,800.00	3,792.29	3,804.29	3,804.29	8.79	8.42	110.99	104.28	20.87	2,373.58	2,356.44	17.13	138.531		
3,900.00	3,891.68	3,903.68	3,903.68	9.06	8.64	111.24	104 28	2,320.87	2,377.54	2,359.92	17.62	134.913		
4,000.00	3,991.08	4,003.08	4,003.08	9.34	8.87	1 48	104/28	2,320.87	2,381.56	2,363.44	18.11	131.484		
4,100.00	4,090.48	4,102.48	4,102.48	9.61	9.09	Th	104.28	2,320.87	2,385.61	2,367.01	18.60	128.231		
4,200.00	4,189.88	8,772.18	6,522.02	9.89	67.42	11.7	170.40	-101.94	2,320.44	2,245.72	74.72	31.056		
4,300.00	4.289.28	8,774.48	6,521.99	10.17	48	171.26	170.40	-104.25	2,221.08	2,145.94	75.14	29.558		
4,400.00	4,388.67	8,776.79	6,521.96	4 5	6. 4	-170.76	170.40	-106.55	2,121.79	2,046.22	75.57	28.078		
4,500.00	4,488.07	8,779.09	6,521.92	73	هر مر	-170.25	170.40	-108.86	2,022.56	1,946.57	75.99	26.618		
4,600.00	4,587.47	8,781.40	6 521.6	1 2	67.67	-169.74	170.40	-111.16	1,923.40	1,847.00	76.40	25.175		
4,700.00	4,686.87	8,783.71	6, 1.85	11.30	67.73	-169.23	170.40	-113.47	1,824.34	1,747.52	76.81	23.750		
4 700 70	4 770 0			44.54	07.70	400.04	470.40	445.40	4 744 47	4 004 04	77.40	00.574		
4,783.73	4,770.0	85.6	6,521.02	11.54	67.78	-168.81	170.40	-115.40	1,741.47	1,664.31	77.16	22.571		
4,800.00	4,786.27	796.00	5,521.82	11.58	67.79	-168.51	170.40	-115.77	1,725.37	1,648.09	77.28	22.326		
4,900.00	4,885.78	8,78,-31	6,521.79	11.80	67.84	-166.53	170.40	-117.67	1,626.37	1,548.38	77.98	20.855		
5,000.00 5,100.00	4,985.46 5,085.25	8,789.21 8,789.92	6,521.77 6,521.76	12.01 12.21	67.88 67.90	-164.28 -161.72	170.40 170.40	-118.98 -119.68	1,527.24 1,428.01	1,448.63 1,348.88	78.61 79.13	19.428 18.046		
5,100.00	3,003.23	0,703.32	0,321.70	12.21	07.50	-101.72	170.40	-115.00	1,420.01	1,540.00	75.15	10.040		
5,200.00	5,185.15	8,790.02	6,521.76	12.40	67.90	-158.78	170.40	-119.78	1,328.68	1,249.18	79.50	16.714		
5,300.00	5,285.11	8,789.51	6,521.77	12.58	67.89	-155.40	170.40	-119.28	1,229.26	1,149.62	79.64	15.435		
5,400.00	5,385.10	8,788.41	6,521.78	12.75	67.86	-151.50	170.40	-118.17	1,129.76	1,050.30	79.47	14.217		
5,412.90	5,398.00	8,788.22	6,521.79	12.77	67.85	-171.14	170.40	-117.99	1,116.92	1,037.51	79.41	14.065		
5,500.00	5,485.10	8,786.93	6,521.81	12.93	67.82	-171.82	170.40	-116.70	1,030.26	950.63	79.63	12.938		
E 600 00	E E05 40	0.705.45	6 504 00	40.44	67.70	470.04	470.40	445.04	000.05	050.00	70.00	44.054		
5,600.00	5,585.10	8,785.45	6,521.83	13.14	67.78 67.74	-172.61 172.40	170.40	-115.21	930.85	850.96 751.44	79.89	11.651		
5,700.00	5,685.10 5,785.10	8,783.96 8,782.48	6,521.85	13.34	67.74 67.70	-173.40 -174.20	170.40	-113.73 -112.25	831.59	751.44 652.14	80.15	10.376		
5,800.00 5,900.00	5,785.10 5,885.10	8,782.48 8,781.00	6,521.87 6,521.89	13.54 13.75	67.70	-174.20 -174.99	170.40 170.40	-112.25 -110.76	732.52 633.74	652.14 553.13	80.39 80.61	9.113 7.861		
6,000.00		8,781.00	6,521.89	13.75	67.62	-174.99	170.40	-110.76	535.42	454.58	80.83	6.624		
0,000.00	0,000.10	0,770.01	0,021.02	15.50	07.02	110.10	170.40	100.20	JJJ.42	-70-7.00	00.03	5.024		
6,100.00	6,085.10	8,778.03	6,521.94	14.16	67.58	-176.59	170.40	-107.80	437.84	356.80	81.04	5.403		
6,200.00	6,185.10	8,776.55	6,521.96	14.37	67.54	-177.39	170.40	-106.31	341.66	260.44	81.23	4.206		
6,300.00	6,285.10	8,775.06	6,521.98	14.58	67.50	-178.20	170.40	-104.83	248.51	167.11	81.41	3.053		
6,400.00	6,385.10	8,773.58	6,522.00	14.78	67.46	-179.00	170.40	-103.35	163.65	82.07	81.58	2.006		
6,500.00	6,485.10	8,772.10	6,522.03	14.99	67.42	-179.80	170.40	-101.86	108.62	26.88	81.73	1.329 L	evel 3	
6 504 00	6 540 00	0 774 70	6 500 00	45.05	67.44	470.00	470.40	404.40	105.70	00.01	04.77	4 000 1	aval 2 CC EC CE	
6,524.93		8,771.73	6,522.03	15.05	67.41 67.27	179.99	170.40	-101.49	105.72	23.94	81.77		evel 3, CC, ES, SF	
6,600.00		8,770.61 8,769.13	6,522.05	15.20	67.37	179.39	170.40	-100.38	129.65	47.77	81.88	1.583		
6,700.00			6,522.07	15.41	67.33 67.20	178.59 177.78	170.40 170.40	-98.90 -97.41	204.49	122.48	82.01 82.13	2.493		
6,800.00 6,900.00		8,767.65 8,766.16	6,522.09 6,522.11	15.62 15.83	67.29 67.25	177.78 176.98	170.40 170.40	-97.41 -95.93	294.65 389.64	212.52 307.40	82.13 82.24	3.588 4.738		
0,500.00	0,000.10	0,700.10	0,022.11	10.03	07.25	170.90	170.40	-90.93	309.04	307.40	02.24	4./30		
7,000.00	6,985.10	8,764.68	6,522.14	16.04	67.21	176.18	170.40	-94.45	486.64	404.30	82.34	5.910		



Anticollision Report



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Sec.13-T4S-R5W Reference Site: 0.00 usft Site Error: Reference Well: #14-13D-45 BTR Well Error: 0.00 usft

Reference Wellbore Wellbore #1 Reference Design: Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference: True

Survey Calculation Method:

Output errors are at

Database:

Offset TVD Reference: Offset Datum

Well #14-13D-45 BTR

WELL @ 6046.00usft WELL @ 6046.00usft

Minimum Curvature

2.00 sigma EDM 5000.1 Single User Db

Offset De	sign	Sec.13	-T4S-R5W	- #13H-13	-45 BTR -	- Wellbore #1	- Design #1						Offset Site Error:	0.00 usft
Survey Prog	ram: 0-M	WD											Offset Well Error:	0.00 usft
Refer		Offs		Semi Major					Dista					
Measured	Vertical	Measured	Vertical	Reference	Offset	Highside	Offset Wellbor		Between	Between	Minimum Separation		Warning	
Depth (usft)	Depth (usft)	Depth (usft)	Depth (usft)	(usft)	(usft)	Toolface (°)	+N/-S (usft)	+E/-W (usft)	Centres (usft)	Ellipses (usft)	Separation (usft)	Factor		
							` '							
7,100.00	7,085.10 7.185.10	8,763.20	6,522.16	16.25 16.47	67.17 67.13	175.38 174.58	170.40	-92.96 -91.48	584.64 683.22	502.22 600.72	82.42 82.50	7.093 8.282		
7,200.00 7,300.00	,	8,761.71 8,760.23	6,522.18 6,522.20	16.47	67.13	174.58	170.40 170.40	-91.48 -90.00	782.16	699.60	82.50	9.474		
7,400.00	7,385.10	8,758.75	6,522.22	16.89	67.05	172.99	170.40	-88.51	881.33	798.72	82.61	10.668		
7,500.00	7,485.10	8,757.26	6,522.25	17.10	67.01	172.20	170.40	-87.03	980.67	898.02	82.65	11.865		
7,600.00	7,585.10	8,755.78	6,522.27	17.31	66.97	171.42	170.40	-85.55	1,080.13	997.45	82.68	13.064		
7,700.00	7,685.10	8,754.30	6,522.29	17.53	66.93	170.63	170.40	-84.06	1,179.68	1,096.98	82.70	14.26		
7,800.00	7,785.10	8,752.81	6,522.31	17.53	66.89	169.85	170.40	-82.58	1,279.30	1,196.59	82.71	15.37		
7,900.00	7,705.10	8 751 33	6 522 33	17.74	66.85	169.03	170.40	-81 10	1,279.50	1 296 27	82-71	6 678		
7,962.90	7.948.00	8.750.40	6.522.35	18.09	66.83	168.59	170.40	-80.16	1.441.69	1.358.99	82	17,432		
				ur	U	170.63 169.85 169.07 168.59								



Anticollision Report



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Sec.13-T4S-R5W Reference Site: 0.00 usft Site Error: Reference Well: #14-13D-45 BTR Well Error: 0.00 usft

Reference Wellbore Wellbore #1

Reference Design: Design #1 Local Co-ordinate Reference:

Well #14-13D-45 BTR TVD Reference: WELL @ 6046.00usft MD Reference: WELL @ 6046.00usft North Reference: True

**Survey Calculation Method:** 

Minimum Curvature 2.00 sigma

Output errors are at EDM 5000.1 Single User Db Database:

Offset TVD Reference: Offset Datum

Offset De Survey Prog	_		143-R3W	- #10-13D	-HODIK	- vvelibore #	1 - Design #1						Offset Site Error: Offset Well Error:	0.00 us
Refer	ence	Offs		Semi Major					Dista					
Depth	Vertical Depth	Measured Depth	Vertical Depth	Reference	Offset	Highside Toolface	Offset Wellbor +N/-S	+E/-W	Between Centres	Between Ellipses	Minimum Separation	Separation Factor	Warning	
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)			
0.00	0.00	11.00	11.00	0.00	0.01	87.05	119.58	2,320.87	2,323.95					
100.00	100.00	111.00	111.00	0.10	0.12	87.05	119.58	2,320.87	2,323.95	2,323.73	0.22	N/A		
200.00	200.00	211.00	211.00	0.32	0.35	87.05	119.58	2,320.87	2,323.95	2,323.28	0.67	3,493.040		
300.00	300.00	311.00	311.00	0.55	0.57	87.05	119.58	2,320.87	2,323.95	2,322.83	1.11	2,084.556		
400.00	400.00	411.00	411.00	0.77 0.99	0.79 1.02	87.05 87.05	119.58	2,320.87	2,323.95	2,322.38 2,321.93	1.56	1,485.546		
500.00	500.00	511.00	511.00	0.99	1.02	67.05	119.58	2,320.87	2,323.95	2,321.93	2.01	1,153.951		
600.00	600.00	611.00	611.00	1.22	1.24	87.05	119.58	2,320.87	2,323.95	2,321.48	2.46	943.37		
700.00	700.00	711.00	711.00	1.44	1.47	87.05	119.58	2,320.87	2,323.95	2,321.03	2.91	97 33		
800.00	800.00	811.00	811.00	1.67	1.69	87.05	119.58	2,320.87	2,323.95	2,320.58	3 36	1.135		
900.00	900.00	911.00	911.00	1.89	1.92	87.05	119.58	2,320.87	2,323.95	2,320.13	3	609.635		
1,000.00	1,000.00	1,011.00	1,011.00	2.12	2.14	87.05	119.58	2,320.87	2,323.95	2,319.	4.26	545.327		
1,100.00	1,100.00	1,111.00	1,111.00	2.34	2.37	87.05	119.58	2,320.87	2,323.95	331 4	4.71	493.292		
1,200.00	1,200.00	1,211.00	1,211.00	2.57	2.59	87.05	119.58	2,320.87	2-323.	18) ਭ	5.16	450.322		
1,300.00	1,300.00	1,311.00	1,311.00	2.79	2.82	87.05	119.58	2,320.87	2,3 .95	,318.34	5.61	414.239		
1,400.00	1,400.00	1,411.00	1,411.00	3.02	3.04	87.05	119.58	2,320	2,32 .95	2.317.89	6.06	383.509		
1,500.00	1,500.00	1,511.00	1,511.00	3.24	3.27	87.05	119.58	2,520 8	323.95	2,317.44	6.51	357.024		
1 600 00	1 600 00	1 644 00	1 644 00	0.47	2.40	07.05	10.50	200.07	2 222 05	2 246 00	6.00	222.000		
1,600.00	1,600.00 1,700.00	1,611.00 1,711.00	1,611.00 1,711.00	3.47 3.69	3.49 3.72	87.05 87.05	119.58 119.58	2,320.87	2,323.95 2,323.95	2,316.99 2,316.54	6.96 7.41	333.960 313.695		
1,700.00 1,800.00	1,800.00	1,711.00	1,811.00	3.99	3.72	87.05	119.58	2,320.87	2,323.95	2,316.54	7.41	295.749		
1,900.00	1,900.00	1,911.00	1,911.00	4.14	4.17		119.58	2,320.87	2,323.95	2,315.64	8.31	279.746		
2,000.00	2,000.00	2,011.00	2,011.00	4.14	4.17	77.0	119.58	2,320.87	2,323.95	2,315.19	8.76	265.385		
0.400.00	0.400.00	0.444.00	0.444.00	4.50			440.50	0.000.07	0.202.05	0.044.74	0.04	050 407 00		
2,100.00 2,200.00	2,100.00 2,199.99	2,111.00 2,210.99	2,111.00 2,210.99	4.59	02	87.05 107.25	119.58 119.58	2,320.87 2,320.87	2,323.95 2,324.21	2,314.74 2,314.55	9.21 9.65	252.427 CC 240.738 ES		
2,300.00	2,199.99	2,310.96	2,310.96	04	5.07	107.23	119.58	2,320.87	2,324.21	2,314.88	10.10	230.176	•	
2,400.00	2,399.86	2,409.25	2 109.2	04	5.29	107.31	119.59	2,320.87	2,326.29	2,315.75	10.10	220.640		
2,500.00	2,499.68	2,500.00	2, 9.99	5.49	5.49	107.47	120.85	2,321.18	2,328.52	2,317.55	10.97	212.282		
2,600.00	2,599.2	79.5	2,579.45	5.72	5.67	107.52	123.68	2,321.88	2,331.89	2,320.52	11.37	205.076		
2,700.00	2,698.90	37.97	2,667.76	5.95	5.87	107.56	128.64	2,323.10	2,336.42	2,324.62	11.80	198.050		
2,729.17	2,727.91	2,65108	2,696.81	6.02	5.93	107.57	130.46	2,323.55	2,337.89	2,325.96	11.93	195.968		
2,800.00	2,798.31	2,767.75	2,767.33	6.19	6.09	107.65	134.87	2,324.63	2,341.53	2,329.27	12.26	191.044		
2,900.00	2,897.71	2,867.53	2,866.90	6.43	6.32	107.75	141.10	2,326.17	2,346.68	2,333.95	12.72	184.448		
3,000.00	2,997.11	2,967.30	2,966.47	6.68	6.54	107.85	147.32	2,327.70	2,351.83	2,338.63	13.19	178.240		
3,100.00	3,096.50	3,067.08	3,066.04	6.93	6.77	107.96	153.55	2,329.23	2,356.99	2,343.32	13.67	172.395		
3,200.00	3,195.90	3,166.86	3,165.61	7.19	7.00	108.06	159.77	2,330.77	2,362.16	2,348.00	14.15	166.889		
3,300.00	3,295.30	3,266.63	3,265.18	7.45	7.23	108.16	166.00	2,332.30	2,367.33	2,352.69	14.64	161.701		
3,400.00	3,394.70	3,366.41	3,364.75	7.71	7.46	108.27	172.23	2,333.83	2,372.52	2,357.39	15.13	156.807		
3,500.00	3,494.09	3,466.18	3,464.32	7.98	7.70	108.37	178.45	2,335.37	2,377.71	2,362.09	15.62	152.188		
3,600.00	3,593.49	3,565.96	3,563.89	8.25	7.93	108.47	184.68	2,336.90	2,382.91	2,366.79	16.12	147.823		
3,700.00	3,692.89	3,665.74	3,663.46	8.52	8.17	108.57	190.90	2,338.43	2,388.11	2,371.49	16.62	143.696		
3,800.00	3,792.29	3,765.51	3,763.03	8.79	8.40	108.67	197.13	2,339.97	2,393.33	2,376.21	17.12	139.789		
3,900.00	3,891.68	3,865.29	3,862.60	9.06	8.64	108.77	203.36	2,341.50	2,398.55	2,380.92	17.63	136.088		
4,000.00	3,991.08	3,965.06	3,962.17	9.34	8.88	108.87	209.58	2,343.03	2,403.78	2,385.64	18.13	132.577		
4,100.00	4,090.48	4,064.84	4,061.74	9.61	9.12	108.97	215.81	2,344.57	2,409.01	2,390.37	18.64	129.244		
4,200.00	4,189.88	4,164.62	4,161.31	9.89	9.36	109.07	222.03	2,346.10	2,414.25	2,395.10	19.15	126.077		
4,300.00	4,289.28	4,264.39	4,260.88	10.17	9.60	109.17	228.26	2,347.63	2,419.50	2,399.84	19.66	123.064		
4,400.00	4,388.67	4,364.17	4,360.45	10.45	9.84	109.26	234.49	2,349.17	2,424.76	2,404.59	20.17	120.195		
4,500.00	4,488.07	4,463.94	4,460.02	10.73	10.08	109.36	240.71	2,350.70	2,430.02	2,409.34	20.69	117.462		
4,600.00	4,587.47	4,563.72	4,559.59	11.02	10.32	109.46	246.94	2,352.24	2,435.29	2,414.09	21.20	114.854		
4,700.00	4,686.87	4,663.50	4,659.16	11.30	10.56	109.56	253.16	2,353.77	2,440.57	2,418.85	21.72	112.365		
4,783.73	4,770.09	4,747.04	4,742.53	11.54	10.77	109.64	258.38	2,355.05	2,445.00	2,422.84	22.15	110.366		
4,800.00	4,786.27	4,763.27	4,758.73	11.58	10.81	109.66	259.39	2,355.30	2,445.85	2,423.61	22.23	110.007		
4.000.00	4 005 75	4.000.41	4.050.05	44.0-	44.05	400 70	205.05	0.050.0:	0.450 ==	0.400.00	22.25	407.004		
4,900.00	4,885.78	4,863.11	4,858.35	11.80	11.05	109.78	265.62	2,356.84	2,450.75	2,428.06	22.69	107.991		



Anticollision Report



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Sec.13-T4S-R5W Reference Site: 0.00 usft Site Error: Reference Well: #14-13D-45 BTR Well Error: 0.00 usft

Reference Wellbore Wellbore #1

Reference Design: Design #1 Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Output errors are at

Database:

Offset TVD Reference:

Well #14-13D-45 BTR

WELL @ 6046.00usft WELL @ 6046.00usft True

Minimum Curvature

2.00 sigma EDM 5000.1 Single User Db

Offset Datum

Offset De	sign	Sec.13-	T4S-R5W	- #16-13D	45 BTR -	- Wellbore #1	- Design #1						Offset Site Error:	0.00 us
Survey Prog	ram: 0-M	WD											Offset Well Error:	0.00 us
Refer	ence	Offse	et	Semi Major	Axis				Dista	ince				
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbor +N/-S (usft)	re Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
5,000.00	4,985.46	4,963.00	4,958.04	12.01	11.29	109.85	271.85	2,358.37	2,455.06	2,431.92	23.15	106.065		
5,100.00	5,085.25	5,062.93	5,057.77	12.21	11.54	109.88	278.09	2,359.91	2,458.78	2,435.19	23.59	104.226		
5,200.00	5,185.15	5,162.86	5,157.49	12.40	11.78	109.86	284.32	2,361.44	2,461.91	2,437.89	24.03	102.468		
5,300.00	5,285.11	5,267.61	5,262.03	12.58	12.03	109.80	290.74	2,363.02	2,464.43	2,439.97	24.45	100.775		
5,400.00	5,385.10	5,386.45	5,380.76	12.75	12.25	109.73	295.44	2,364.18	2,465.80	2,440.95	24.85	99.219		
5,412.90	5,398.00	5,401.79	5,396.10	12.77	12.28	89.54	295.79	2,364.27	2,465.88	2,440.98	24.90	99.027		
5,500.00	5,485.10	5,501.79	5,496.10	12.93	12.45	89.52	296.62	2,364.47	2,466.06	2,440.82	25.24	97.71		
5,600.00	5,585.10	5,601.79	5,596.10	13.14	12.67	89.52	296.62	2,364.47	2,466.06	2,440.40	25.66	96 37		
5,700.00	5,685.10	5,701.79	5,696.10	13.34	12.89	89.52	296.62	2,364.47	2,466.06	2,439.98	26 08	1,552		
5,800.00	5,785.10	5,801.79	5,796.10	13.54	13.10	89.52	296.62	2,364.47	2,466.06	2,439.56	26.5	93.043		
5,900.00	5,885.10	5,901.79	5,896.10	13.75	13.32	89.52	296.62	2,364.47	2,466.06	2,439.	6.93	91.578		
6,000.00	5,985.10	6,001.79	5,996.10	13.96	13.54	89.52	296.62	2,364.47	2,466.06	343 1	27.35	90.157		
6,100.00	6,085.10	6,101.79	6,096.10	14.16	13.75	89.52	296.62	2,364.47	2.466.	38_0	27.78	88.776		
6,200.00	6,185.10	6,201.79	6,196.10	14.37	13.97	89.52	296.62	2,364.47	2, 08	,437.86	28.20	87.435		
6,300.00	6,285.10	6,301.79	6,296.10	14.58	14.19	89.52	296.62	2,334	2,46 06	2,437.43	28.63	86.131		
6,400.00	6,385.10	6,401.79	6,396.10	14.78	14.41	89.52	296.62	2,5.44	166.06	2,437.00	29.06	84.864		
6,500.00	6,485.10	6,501.79	6,496.10	14.99	14.63	89.52	296.62	364.47	2,466.06	2,436.57	29.49	83.631		
6,600.00	6,585.10	6,601.79	6,596.10	15.20	14.85	89.52	296 62	2,364.47	2,466.06	2,436.14	29.92	82.433		
6,700.00	6,685.10	6,701.79	6,696.10	15.41	15.06	8 52	296.62	2,364.47	2,466.06	2,435.71	30.35	81.266		
6,800.00	6,785.10	6,801.79	6,796.10	15.62	15.28	<b>6</b> 5.	296.62	2,364.47	2,466.06	2,435.28	30.78	80.131		
6,900.00	6,885.10	6,901.79	6,896.10	15.83	15.50	9.5.	296.62	2,364.47	2,466.06	2,434.85	31.21	79.025		
7,000.00	6,985.10	7,001.79	6,996.10	16.04	72	89.52	296.62	2,364.47	2,466.06	2,434.42	31.64	77.949		
7,100.00	7,085.10	7,101.79	7,096.10	1,25	1. 4	89.52	296.62	2,364.47	2,466.06	2,433.99	32.07	76.900		
7,200.00	7,185.10	7,201.79	7,196.10	47	16.16	89.52	296.62	2,364.47	2,466.06	2,433.56	32.50	75.877		
7,300.00	7,285.10	7,301.79	7 296.	1 8	16.38	89.52	296.62	2,364.47	2,466.06	2,433.13	32.93	74.881		
7,400.00	7,385.10	7,401.79	7, 6.10	16.89	16.60	89.52	296.62	2,364.47	2,466.06	2,432.69	33.37	73.909		
7,500.00	7,485.1	01.7	7,496.10	17.10	16.82	89.52	296.62	2,364.47	2,466.06	2,432.26	33.80	72.962		
7,600.00	7,585.10	201.79	,596.10	17.31	17.04	89.52	296.62	2,364.47	2,466.06	2,431.83	34.23	72.037		
7,700.00	7,685.10	7,7019	7,696.10	17.53	17.26	89.52	296.62	2,364.47	2,466.06	2,431.39	34.67	71.135		
7,800.00	7,785.10	,801.79	7,796.10	17.74	17.48	89.52	296.62	2,364.47	2,466.06	2,430.96	35.10	70.254		
7,900.00	7,885.10	7,901.79	7,896.10	17.96	17.70	89.52	296.62	2,364.47	2,466.06	2,430.52	35.54	69.394		
7,962.90	7,948.00	7,964.70	7,959.00	18.09	17.84	89.52	296.62	2,364.47	2,466.06	2,430.25	35.81	68.864 SI	=	



Anticollision Report



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Sec.13-T4S-R5W Reference Site: Site Error: 0.00 usft #14-13D-45 BTR Reference Well: Well Error: 0.00 usft

Reference Wellbore Wellbore #1 Reference Design:

Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Output errors are at

Database:

Offset TVD Reference:

Well #14-13D-45 BTR WELL @ 6046.00usft

WELL @ 6046.00usft

Minimum Curvature

2.00 sigma EDM 5000.1 Single User Db

Offset Datum

Reference Depths are relative to WELL @ 6046.00usft


Offset Depths are relative to Offset Datum

Central Meridian is 111° 30' 0.000 W

Coordinates are relative to: #14-13D-45 BTR

Coordinate System is US State Plane 1927 (Exact solution), Utah Central 4302

Grid Convergence at Surface is: 0.70°





Anticollision Report



Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27)

Sec.13-T4S-R5W Reference Site: Site Error: 0.00 usft #14-13D-45 BTR Reference Well: Well Error: 0.00 usft Reference Wellbore Wellbore #1

Well #14-13D-45 BTR Local Co-ordinate Reference: TVD Reference: WELL @ 6046.00usft MD Reference: WELL @ 6046.00usft

North Reference: True

**Survey Calculation Method:** Minimum Curvature 2.00 sigma

Output errors are at

Database: EDM 5000.1 Single User Db

Offset TVD Reference: Offset Datum

Reference Depths are relative to WELL @ 6046.00usft

Design #1

Offset Depths are relative to Offset Datum


Central Meridian is 111° 30' 0.000 W

Reference Design:

Coordinates are relative to: #14-13D-45 BTR

Coordinate System is US State Plane 1927 (Exact solution), Utah Central 4302

Grid Convergence at Surface is: 0.70°



## **SURFACE USE PLAN**

# BILL BARRETT CORPORATION 14-13D-45 BTR

SE SW, 532' FSL and 2080' FWL, Section 13, T4S-R5W (surface hole) SE SW, 810' FSL and 1980' FWL, Section 13, T4S-R5W (bottom hole) Duchesne County, Utah

The onsite inspection for this pad occurred on February 1, 2012. This is a new pad with one proposed well. Plat changes and site specific stipulations requested at the onsite are reflected within this APD and summarized below.

- a) Relocated topsoil from corners 7 & 8 area to corners 3 & 4 area, omitted topsoil from corners C & 6 area to maximize interim reclamation and minimize topsoil loss;
- b) Shorten trailer side of the pad area 10 feet to minimize fill slopes;

The excavation contractor would be provided with an approved copy of the surface use plan of operations before initiating construction.

## 1. Existing Roads:

- a. The proposed well site is located approximately 4.3 miles south of Duchesne, Utah. Maps and direction reflecting the route to the proposed well site are included (see Topog uphic maps A and B).
- b. The existing Set maintained Highway 191 would be utilized from Duchesne for 2.31 lies and existing Duchesne County maintained Sowers Canyon Road.

  The Sewers Canyon Road would be utilized for 1.9 miles to the planned new access road.
- c. Project roads would require routine year-round maintenance to provide year-round access. Maintenance would include inspections, reduction of ruts and holes, maintenance to keep water off the road, replacement of surfacing materials, and clearing of sediment blocking ditches and culverts. Should snow removal become necessary, roads would be cleared with a motor grader and snow would be stored along the down gradient side to prohibit runoff onto the road. Aggregate would be used as necessary to maintain a solid running surface and minimize dust generation.
- d. Vehicle operators would obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions. Travel would be limited to the existing access roads and proposed access road.
- e. The use of roads under Utah State and Duchesne County maintenance are necessary to access the project area with no improvements proposed. A Duchesne County Road Department access will be obtained.

f. All existing roads would be maintained and kept in good repair during all phases of operation.

#### 2. Planned Access Road:

- a. Approximately 254 feet of new access road is planned from the Duchesne County maintained Sowers Canyon road (see Topographic Map B). The proposed access road crosses entirely Ute Tribe surface.
- b. The planned access road would be constructed to a 30-foot ROW width with an 18-foot travel surface. See section 12.d. below for disturbance estimates.
- c. New road construction and improvements of existing roads would typically require the use of motor graders, crawler tractors, 10-yard end dump trucks, and water trucks. The standard methodology for building new roads involves the use of a crawler tractor or track hoe to windrow the vegetation to one side of the road corridor, remove topsoil to the opposing side of the certifical and rough-in the roadway. This is followed by a grader or bulldozer to stablish barrow ditches and crown the road surface. Where culverts pre-required, a track hoe or backhoe would trench the road and install the unjects. Some hand labor would be required when installing and armoring clawerts, Road base or gravel in some instances would be necessary and would be healed in and a grader used to smooth the running surface.
- d. The proposed road would be constructed to facilitate drainage, control erosion and minimized isyan impacts by following natural contours where practical. No unnecess typide-casting of material would occur on steep slopes.
- minimum grade of 10% would be maintained throughout the project with minimum cuts and fills, as necessary, to access the well.
- f. Excess rock from construction of the pad may be used for surfacing of the access road if necessary. Any additional aggregate necessary would be obtained from private or State of Utah lands in conformance with applicable regulations. Aggregate would be of sufficient size, type, and amount to allow all weather access and alleviate dust.
- g. Where topsoil removal is necessary, it would be windrowed (i.e. stockpiled/accumulated along the edge of the ROW and in a low row/pile parallel with the ROW) and re-spread over the disturbed area after construction and backfilling are completed. Vegetation removed from the disturbed area would also be re-spread to provide protection, nutrient recycling, and a seed source for reclamation.
- h. Turnouts are not proposed.

- i. No culverts and no low-water crossings are anticipated. Adequate drainage structures, where necessary, would be incorporated into the remainder of the road to prevent soil erosion and accommodate all-weather traffic.
- j. No gates or cattle guards are anticipated at this time.
- k. Surface disturbance and vehicular travel would be limited to the approved location access road. Adequate signs would be posted, as necessary, to warn the public of project related traffic.
- All access roads and surface disturbing activities would conform to the appropriate standard, **no higher than necessary**, to accommodate their intended function adequately as outlined in the Bureau of Land Management and Forest Service publication: <u>Surface Operating Standards for Oil and Gas Exploration and Development</u>, Fourth Edition – Revised 2007.
- m. The operator would be responsible for all maintenance needs of the new access road.
- 3. <u>Location of Existing Wells (see One-Mile Radius 1).</u>
  - a. Following is a list of wells with the could ocations within a one-mile radius of the proposed pad:

i. water wells	none
ii. inject in wens	none
ii. d sp. sal wells	none
i drilling wells	none
v. temp shut-in wells	none
vi. producing wells	none
vii. abandoned wells	three

#### 4. Location of Production Facilities

Retu

- a. Surface facilities would consist of a wellhead, separator, gas meter, combustor, (1) 500 gal methanol tank, (1) 500 glycol tank, (3) 500 bbl oil tanks, (1) 500 bbl water tank, (1) 500 bbl test tank, (1) 1000 gal propane tank, a pumping unit or Roto-flex unit or ESP or gas lift unit, electrical or with a natural gas or diesel fired motor, solar panels, solar chemical and methanol pumps and one trace pump. See attached proposed facility diagram.
- b. Most wells would be fitted with a pump jack or Roto-flex unit or ESP or gas lift to assist liquid production. The prime mover for pump jacks or Roto-flex units would be small (100 horsepower or less), electric motor or natural gas or diesel fired internal combustion engines. If a gas lift is installed, it would be set on a 10 ft x 25 ft pad and the prime mover would be a natural gas-fired internal combustion engine rated at 200 horsepower or less or an electric compressor of similar horsepower powered by electricity.

- c. The tank battery would be surrounded by a secondary containment berm of sufficient capacity to contain 1.1 times the entire capacity of the largest single tank and sufficient freeboard to contain precipitation. All loading lines and valves would be placed inside the berm surrounding the tank battery or would utilize catchment basins to contain spills. All liquid hydrocarbon production and measurement shall conform to the provisions of 43 CFR 3162.7-2 and Onshore Oil and Gas Order No. 4 for the measurement of oil.
- d. Gas meter run(s) would be constructed and located on lease within 500 feet of the wellheads. Meter runs would be housed and/or fenced. As practicably feasible, meters would be equipped with remote telemetry monitoring systems. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- e. A combustor may be installed at this location for control of associated condensate tank emissions. A combustor ranges from 24 the es to 48 inches wide and is approximately 27 ft tall. Combustor procedent would be on existing disturbance.
- f. Approximately 2,979 feet of pipe in a condo containing up to three lines (one gas pipeline up to 8 inch a diameter, one water line up to 4 inch in diameter and one residue line up to 4 inc in diameter) is proposed traversing west to the proposed 16-14D-45 the pipeline corridor. The proposed 16-14D-45 BTR pipeline corridor (see Topographic Map C). Pipelines would be constituted of steel, polyethylene or fiberglass and would connect to the proposed pipeline servicing nearby BBC wells. The pipeline crosses entirely the Tribe surface.
- g. The new segment of gas pipeline would be surface laid within a 30 foot wide pipeline corridor adjacent to the proposed access road. See 12.d below for disturbance estimates.
- h. Construction of the ROW would temporarily utilize the 30 foot disturbed width for the road for a total disturbed width of 60 foot for the road and pipeline corridors. The use of the proposed well site and access roads would facilitate the staging of the pipeline construction.
- Pipeline construction methods and practices would be planned and conducted by BBC with the objective of enhancing reclamation and fostering the reestablishment of the native plant community.
- j. All permanent above-ground structures would be painted a flat, non-reflective color, such as Beetle Green, to match the standard environmental colors. All facilities would be painted the designated color at the time of installation.

Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.

- k. Site security guidelines identified in 43 CFR 3162.7-5 and Onshore Oil and Gas Order No. 3 would be adhered to. Any modifications to proposed facilities would be reflected in the site security diagram submitted.
- 1. The site would require periodic maintenance to ensure that drainages are kept open and free of debris, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.
- 5. <u>Location and Type of Water Supply:</u>

a. Water for the drilling and completion would be trucked from any of the following locations:

Water Dight No. and	Vater Right No. and					
Water Right No. and Application or Change No.	Applicant	Allocation	Da	Diversion	Source	
43-180	Duchesne City Water Service District	5 cfs	TE 20.04	Knight Diversion Dam	Duchesne River	
43-1202, Change a13837	Myton C.	5 92 fr and 3967 acre feet	3/21/1986	Knight Diversion Dam	Duchesne River	
43-10444, Appln A57477	I uch sne county Upper Country Water	2 cfs	1994	Ditch at Source	Cow Canyon Spring	
43-10446, Apple 1-774-2	Duchesne County Upper Country Water	1.58 cfs	1994	Ditch at Source	Cow Canyon Spring	
8-12-3, Appln A17462	J.J.N.P. Company	7 cfs	1946	Strawberry River	Strawberry River	
43-1273, Appln t36590	J.J.N.P. Company	4 cfs	6/03/2010	Strawberry River	Strawberry River	
43-2505, Appln t37379	McKinnon Ranch Properties, LC	1.3 cfs	4/28/2011	Pumped from Sec, 17, T4SR6W	Water Canyon Lake	
43-12415, Change A17215a	Peatross Ranch, LLC	1.89 cfs	09/2011	Dugout Pond	Strawberry River	

- b. No new water well is proposed with this application.
- c. Should additional water sources be pursued they would be properly permitted through the State of Utah Division of Water Rights.

d. Water use would vary in accordance with the formations to be drilled but would be up to approximately 5.41 acre feet for drilling and completion operations.

#### 6. Source of Construction Material:

- a. The use of materials would conform to 43 CFR 3610.2-3.
- b. No construction materials would be removed from the lease or EDA area.
- c. If any additional gravel is required, it would be obtained from a local supplier having a permitted source of materials within the general area.

#### 7. <u>Methods of Handling Waste Disposal:</u>

- a. All wastes associated with this application would be contained and discost of utilizing approved facilities.
- b. The reserve pit would be constructed so as not to leak or allow any discharge.
- c. The reserve would be lined with 12 m 1 m in lum, thickness polyethylene nylon reinforced liner material. The line () could everlay straw, dirt and/or bentonite if rock is encountered during excapation. The liner would overlap the pit walls and be covered with dirt are vor rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit. A minimum or two feet of free board would be maintained between the maximum field level and the top of the reserve pit at all times.
  - Volleter livestock from entering the pit, the three sides exterior to the location would be fenced before drilling starts. Following the conclusion of drilling and completion activities, the fourth side would also be fenced.
- e. Drill cuttings would be contained in the pit and buried on-site for a period not to exceed six months, weather permitting
- f. Produced fluids from the well other than water would be decanted into steel test tank(s) until such time as construction of production facilities is completed. Any oil that may be accumulated would be transferred to a permanent production tank. Produced water may be used in further drilling and completion activities, evaporated in the pit, or would be hauled to one of the following state-approved disposal facilities:

#### **Disposal Facilities**

- 1. RNI Industries, Inc. Pleasant Valley Disposal Pits, Sec. 25, 26, 35 & 36, T4S-R3W
- 2. Pro Water LLC Blue Bench 13-1 Disposal Well (43-013-30971) NENE, Sec. 13, T3S-R5W

#### **Disposal Facilities**

- 3. RN Industries, Inc. Bluebell Disposal Ponds, Sec. 2, 4 & 9, T2S-R2W
- 4. Water Disposal, Inc. Harmston 1-32-A1 Disposal Well (43-013-30224), UTR #00707, Sec. 32, T1S-R1W
- 5. Unified Water Pits Sec. 31, T2S-R4W
- 6. Iowa Tank Line Pits 8500 BLM Fence Road, Pleasant Valley
- 7. Western Water Solutions Sand Pass Ranch, Sections 9 and 10, T4S-R1W, permit #WD-01-2011
- g. Any salts and/or chemicals, which are an integral part of the drilling system, would be disposed of in the same manner as the drilling fluid.
- h. Any spills of oil, condensate, produced or frac water, drilling fluids, or other potentially deleterious substances would be recovered and either return do its origin or disposed of at an approved disposal site, most likely in Domesic, Utah.
- i. Chemicals on the EPA's Consolidated List of Chemicals tubect to reporting under Title III of the Superfund Amendments and the authorization Act of 1986 (SARA) may be used or stored in quantities a tense portable quantities. In the course of drilling, BBC could potentially state and use diesel fuel, sand (silica), hydrochloric acid, and CO<sub>2</sub> gas, all less medias hazardous substances in 40 CFR Part 302, Section 302.4, requantities exceeding 10,000 pounds. In addition, natural gas condens to and rude oil and methanol may be stored or used in reportable quantities. Small quantities of retail products (paint/spray paints, solvents { cg., WD=0}, and lubrication oil) containing non-reportable volumes of hazardous substances may be stored and used on site at any time. No expressly hazardous substances, as defined in 40 CFR 355, would be used, troduced, stored, transported or disposed of in association with the drilling, testing or completion of the wells.
- j. Portable toilets and trash containers would be located onsite during drilling and completion operations. A commercial supplier would install and maintain portable toilets and equipment and would be responsible for removing sanitary waste. Sanitary waste facilities (i.e. toilet holding tanks) would be regularly pumped and their contents disposed of at approved sewage disposal facilities in Duchesne, and/or Uintah Counties, in accordance with applicable rules and regulations regarding sewage treatment and disposal. Accumulated trash and nonflammable waste materials would be hauled to an approved landfill once a week or as often as necessary. All debris and waste materials not contained in the trash containers would be cleaned up, removed from the construction ROW, well pad, or worker housing location, and disposed of at an approved landfill. Trash would be cleaned up everyday.
- k. Sanitary waste equipment and trash bins would be removed from the Project Area upon completion of access road or pipeline construction; following drilling and completion operations at an individual well pad; when worker housing is no longer needed; or as required.

- 1. A flare pit may be constructed a minimum of 110' from the wellhead(s) and may be used during completion work. In the event a flare pit proves to be unworkable, a temporary flare stack or open top tank would be installed. BBC would flow back as much fluid and gas as possible into pressurized vessels, separating the fluids from the gas. In some instances, due to the completion fluids utilized within the Project Area, it is not feasible to direct the flow stream from the wellbore through pressurized vessels. In such instances BBC proposes to direct the flow to the open top tanks until flow through the pressurized vessels is feasible. At which point the fluid would either be returned to the reserve pit or placed into a tank(s). The gas would be directed to the flare pit, flare stack (each with a constant source of ignition), or may be directed into the sales pipeline.
- m. Hydrocarbons would be removed from the reserve pit would as soon as practical. In the event immediate removal is not practical, the reserve pit would be farged overhead or covered with wire or plastic mesh to protect migrating birds.

## 8. <u>Ancillary Facilities:</u>

- a. Garbage containers and portable toilets we get be eated on the well pad.
- b. On well pads where active drellies and completion is occurring, temporary housing would be provided on location for the well pad supervisor, geologist, tool pusher, and offers that are required to be on location at all times. The well pad could include up a five single wide mobile homes or fifth wheel campers/trailes.
- c. A subject powerline corridor 3,101 feet in length is proposed for installation by high-party installer within a 150 foot wide powerline corridor adjacent to the proposed access road. See 12.d below for disturbance estimates. The powerline crosses entirely Ute Tribe surface.

#### 9. Well Site Layout:

- a. The well would be properly identified in accordance with 43 CFR 3162.6.
- b. The pad layout, cross section diagrams and rig layout are enclosed (see Figures 1 and 2).
- c. The pad and road designs are consistent with industry specifications.
- d. The pad has been staked at its maximum size of 400 feet x 295 feet with an inboard reserve pit size of 205 feet x 100 feet x 8 feet deep. See section 12.d below for disturbance estimates.
- e. Within the approved well pad location, a crawler tractor would strip whatever topsoil is present and stockpile it along the edge of the well pad for use during reclamation. Vegetation would be distributed along the sides of the well pad.

- f. Fill from pit excavation would be stockpiled along the edge of the pit and the adjacent edge of the well pad.
- g. Use of erosion control measures, including proper grading to minimize slopes, diversion terraces and ditches, mulching, terracing, riprap, fiber matting, temporary sediment traps, and broad-based drainage dips or low water crossings would be employed by BBC as necessary and appropriate to minimize erosion and surface runoff during well pad construction and operation. Cut and fill slopes would be constructed such that stability would be maintained for the life of the activity.
- h. All cut and fill slopes would be such that stability can be maintained for the life of the activity.
- i. Diversion ditches would be constructed, if necessary, around the walk site to prevent surface waters from entering the well site area.
- j. Water application may be implemented if necessary to minimize the amount of fugitive dust.
- k. All surface disturbing activities—or ld of supervised by a qualified, responsible company representative was is as we of the terms and conditions of the APD and specifications in the approved plans.
- 10. Plan for Restoration of the Surface:
  - a. A site specific reclamation plan would be submitted, if requested, within 90 days function construction to the surface managing agency.
  - b. Site reclamation would be accomplished for portions of the well pad not required for the continued operation of the well on this pad within six months of completion, weather permitting.
  - c. The operator would control noxious weeds along access road use authorizations and well site by spraying or mechanical removal, according to the Utah Noxious Weed Act and as set forth in the approved surface damage agreements.
  - d. Rat and mouse holes would be filled and compacted from bottom to top immediately upon release of the drilling rig from location. Upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1. The reserve pit would be allowed to dry prior to the commencement of backfilling work. No attempts would be made to backfill the reserve pit until it is free of standing water. Once dry, the liner would be torn and perforated before backfilling.
  - e. The reserve pit and that portion of the location not needed for production facilities/operations would be recontoured to the approximate natural contours.

Areas not used for production purposes would be backfilled and blended into the surrounding terrain, reseeded and erosion control measures installed. Mulching, erosion control measures and fertilization may be required to achieve acceptable stabilization. Back slopes and fore slopes would be reduced as practical and scarified with the contour. The reserved topsoil would be evenly distributed over the slopes and scarified along the contour. Slopes would be seeded with the Ute Tribe specified seed mix.

f. Topsoil salvaged from the drill site and stored for more than one year would be placed at the location indicated on the well site layout drawing and graded to a depth optimum to maintain topsoil viability, seeded with the Ute Tribe prescribed seed mixture and covered with mulch for protection from wind and water erosion and to discourage the invasion of weeds.

# 11. <u>Surface and Mineral Ownership:</u>

- a. Surface ownership Ute Indian Tribe 988 South 7500 East: F. Duchesne, Utah 84026; 435-725-4982.
- b. Mineral ownership Ute Indian Tribe 98°5 ut 300 East; Ft. Duchesne, Utah 84026; 435-725-4982.

### 12. <u>Other Information:</u>

- a. Montgomery Archeological Consultants has conducted a Class III archeological survey. A control the report has been submitted under separate cover to the appropriate byencies by Montgomery as report 11-177 dated June 27, 2011.
- would require that their personnel, contractors, and subcontractors to comply with Federal regulations intended to protect archeological and cultural resources.
- c. Project personnel and contractors would be educated on and subject to the following requirements:
  - No dogs or firearms within the Project Area.
  - No littering within the Project Area.
  - Smoking within the Project Area would only be allowed in off-operator
    active locations or in specifically designated smoking areas. All cigarette
    butts would be placed in appropriate containers and not thrown on the
    ground or out windows of vehicles; personnel and contractors would abide
    by all fire restriction orders.
  - Campfires or uncontained fires of any kind would be prohibited.
  - Portable generators used in the Project Area would have spark arrestors.

### d. Disturbance estimates:

### **Approximate Acreage Disturbances**

Well Pad		3.667	acres
Access	254 feet	0.156	acres
Pipeline	2,979 feet	2.030	acres
Powerline	3,101 feet	10.569	acres

Total 16.422 acres



Bill Barrett Corporation Surface Use Plan 14-13D-45 BTR Duchesne County, UT

#### **OPERATOR CERTIFICATION**

#### Certification:

I hereby certify that I, or someone under my direction supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein would be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application and that bond coverage is provided under Bill Barrett Corporations federal nationwide bond. These statements are subject to the provisions of 18 U.S.C. 1001 for the filings of false statements.

Executed this

Name:

day of \_\_\_\_\_\_\_ 2012 Venessa Langmacher

Position Title:

Senior Permit Analyst

Address:

1099 18<sup>th</sup> Street, Suite 2300, Denver, CO 80202

Telephone:

E-mail:

Field Representative

Returned

Address: Telephone:


E-mail:

Venessa Langmacher, Senior Permit Analyst

Page 12


## **BILL BARRETT CORPORATION**

### TYPICAL 5,000 p.s.i. BLOWOUT PREVENTER



## **BILL BARRETT CORPORATION**

TYPICAL 5,000 p.s.i. CHOKE MANIFOLD





June 21, 2012

Ms. Diana Mason – Petroleum Technician State of Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210 P. O. Box 145801 Salt Lake City, Utah 84114-5801

Re:

Directional Drilling R649-3-11

Blacktail Ridge Area #14-13D-45 BTR Well

Surface: 532' FSL & 2080' FWL, SESW, 13-T4S-R5W, USM Bottom Hole: 810' FSL & 1980' FWL, SESW, 13-T4S-R5W, USM

Duchesne County, Utah

Dear Ms. Mason,

Pursuant to the filing of Bill Barrett Corporation's ("BBC") Application for Permit to Drill the above referenced well, we hereby submit this letter in accordance with Oil & Gas Conservation Rules R649-2, R649-3, R649-10 and R649-11, pertaining to the Location and Siting of Wells.

The proposed location is within our Blacktail Ridge Area.

- BBC is permitting this well as a directional well in order to minariae surface disturbance. By locating the well at the surface location and directional crilling from this location, BBC will be able to utilize the existing road and single in the area.
- The well will be drilled under an Exploration and Deve op ment Agreement between the Ute Indian Tribe and Ute Distribution Corporation. Use Energy, LLC owns a right to participate in this well.
- BBC certifies that it is the working interest wher of all lands within 460 feet of the proposed well location, and together with Ute Energy, LLC, we own 100% of the working interest in these lands.


Based on the nit rolling provided, BBC requests that the permit be granted pursuant to R649-3-11. Should outlieve any questions or need further information, please contact me at 303-312-8544.


Sincerely,


**David Watts** 


Landman


1099 18<sup>TH</sup> STREET SUITE 2300 DENVER, CO 80202 P 303.293.9100 F 303.291.0420













# State of Utah

#### DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA Division Director

June 28, 2012

BILL BARRETT CORP 1099 18th Street Ste 2300 Denver, CO 80202

Re: Application for Permit to Drill - DUCHESNE County, Utah

Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the 14-13D-45 BTR ll, API 43013514950000 that was submitted June 21, 2012 is ng returned unapproved. If you plan on drilling this well in that are, you must first submit a new application. well, API 43013514950000 that was submitted June 21, 201 being returned unapproved. If you plan on drilling this we future, you must first submit a new application.

Should you have any questions reg is matter, please call me Return at (801) 538-5312.

Sincerely,

Diana Mason **Environmental Scientist** 

Enclosure

Bureau of Land Management, Vernal, Utah





# State of Utah

### DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

June 29, 2012

BILL BARRETT CORP 1099 18th Street Ste 2300 Denver, CO 80202

Re: Application for Permit to Drill - DUCHESNE County, Utah

Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the 14-13D-45 BTR well, API 43013514950000 that was submitted June 21, 2012 is being returned unapproved. If you plan on drilling this well in the future, you must first submit a new application.

Should you have any questions regarding this matter, please call me at (801) 538-5312.

Sincerely,

Diana Mason Environmental Scientist

Enclosure

cc: Bureau of Land Management, Vernal, Utah

